



EAP Curtain Wall Systems

Test Results for EAP 100HP Series Curtain Wall System

CSA Standard A440-98

Section 10.2	Air Tightness	Passed Fixed
Section 10.3	Water Tightness	Passed B7
Section 10.4	Wind Load Resistance	Passed C5

CSA Standard A440.2-98

Section 5	Overall U-value*	0.79 W/m ² •°C (0.1392 Btu/Ft ² •h•°F)
-----------	------------------	--

Test Reports are available on request.

*U-value stated above is for 5.76 m² frame size
Overall U-value for reference size is 0.87 W/m²•°C (0.1533 Btu/Ft²•h•°F)

EAP Head Office and Manufacturing Plant:

3620 Blackburn Road S.E.
Calgary, Alberta, Canada T2G 4A5
Ph: (403) 287-4480
Fx: (403) 243-2198
Internet: www.ferguson.ca